

JAWAHARLAL NEHRU UNIVERSITY
ENGINEERING DEPARTMENT
SCHEDULE OF QUANTITY

F.No.4 (34)/10/E/Vol.-I/Engg./2024-25

REGISTERED POST

28.09.2026

Sealed item rate quotations are invited from the eligible electrical contractors having valid electrical contractor License for the work mentioned below. The quotations are to be received on 12.10.2026 at 3:00 pm in R.No.-149 of Admin. Building, JNU and the same shall be opened at 3:30 pm on the same day.

Name of Work:- Installation of Water level indicator in the 112 Unit Multistory Building , JNU.


S. No.	Description of Items	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	Supplying and fixing of following sizes of medium class PVC conduit along with accessories in surface /recess including cutting the wall and making good the same in case of recessed conduit as required.				
1.1	20 mm	350	Meter		
2	Supplying and drawing following pair 0.5 mm dia FRLS/HFFR PVC insulated annealed copper conductor, unarmored cable in the existing surface/ recessed steel/ PVC conduit as required.				
2.1	4 Pair	400	Meter		
3	Supply, installation, testing and commissioning of Water Level indicator equipped with a loud built in audio alarm using an independent manual switch, voltage range of 160 V to 290 V AC (50Hz) including 4-level LED visual display that accurately tracks the tank's water level at 25%, 50%, 75% & 100% capacity with Buzzer Alarm to indicate the overflow of water alongside a dedicated power indicator light to be fixed on 2 mm thick M.S. Plate, installation of circuit wiring on board & tank with high precision water level sensors(probe) in the tank for each level with stainless steel nut/bolt/clamp on the wall of tank complete etc. as required.	8	Each		
4	Supplying and drawing following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in the existing surface/ recessed steel/ PVC conduit as required.				
4.1	3 x 1.5 sq. mm	50	Meter		
5	Supplying and fixing metal box of 150mm X 75mm X 60mm deep (nominal size) on surface or in recess with suitable size of phenolic laminated sheet cover in front including providing and fixing 3 pin 5/6 A socket outlet and 5/6 A piano type switch, connections, painting etc. as required.	8	Each		
	Total				

Conditions:-

1. The quotation for the work shall remain open for a period of 30 days from the date of opening of quotations. The EMD amount shall be forfeited absolutely if contractor back out from the bid before validation period.
2. The work shall be carried out as per specifications defined in the NIQ.
3. All taxes shall be deducted as per Govt. of India rules applicable.
4. Time allowed for completion of above work is **30 days**.
5. Earnest Money amounting to **Rs.2191/-** should be deposited in the shape of Pay Order/Banker's Cheque/Demand Draft in favour Finance Officer, JNU. No quotation will be entertained without Earnest Money.
6. A Price preference upto 5% (with reference to the lowest valid quotation) shall be allowed in favor of individual SC/ST enlisted / non-enlisted contractor. No earnest money is required to be deposited as per O.M. No. DG/CON/Maintenance 2023/09 dated 03.06.2024, subject to submission of valid caste certificate with quotation.
7. Security deposit @7.5% of quoted amount shall be recovered from the bills paid to the agency and the same shall be refunded after defect liability period of three months.
8. **The Quotation shall be placed in sealed envelope marked "Quotation" which shall be submitted with the name of work and due date of opening written on envelope.**
9. The firm has to produce self-attested copies of all relevant documents such as PAN no., GST Registration, SC/ST caste certificate if applicable etc. along with the quotation.
10. The quoted rates shall be inclusive of all taxes, cartage etc and nothing shall be paid extra over / above quoted rates.
11. Payment shall be made after satisfactory completion of work.


28/9/26

Assistant Engineer (E)


28/9/26

Executive Engineer (E)